



E14 Mt Aitken to Mt Ridley Pipeline

Project start date: September 2011
Project completion date: May 2012

Client	Yarra Valley Water
Comdain's role	Principal Contractor
Project description	Construction of approximately 2,400 m of the M687 potable water main, and approximately 1,000 m of the M689 Class A recycled water main, in the road reserve of Aitken Blvd, Craigieburn.
Works undertaken	<ul style="list-style-type: none">Construction of 2.5 km DN825 MSCL potable water mainsConstruction of 1.1 km DN225/300 PE Class A recycled water mainsImplementation of strict traffic and environmental controls to manage local traffic on major roadways and disruption in residential area.
Highlights & Innovations	<ul style="list-style-type: none">Impeccable safety record. No lost time injuries with over 12,000 man hours.Exceptional stakeholder management and communication between all stakeholders using a successful consultative approach.Modification of construction methodology in consideration to residents with regards to vibration even though acceptable by all standards.Managing multiple construction resources and plant to enable efficient, safe and quality pipeline installation.

For more information contact:

Simon Maher

General Manager, Civil

03 8405 0000 | 0417 560 582 | smaher@comdain.com.au | Comdaininfrastructure.com.au

